

Netherlands

# Amsterdam South East

**Location details**

**Address:** Amsterdam South East  
 Kuiperbergweg 13  
 1101 AE, Amsterdam  
 Netherlands

---

**Telephone:** +31 (0) 20 564 0800

---

**Facsimile:** +31 (0) 20 564 0801

---

**Website:** www.telecitcity.nl

---

**Email:** info@telecitcity.nl

---

**Location:** The facility is located within the commercial area of Kuiperbergweg; the centre of Amsterdam and Schipol Airport are approximately 15km away.

---

**Description:** The building was constructed in the 1970's; TeleCity occupies the whole building. The construction of the building is steel framed with external thermal insulated cladding with internal lining.

**Commercial details**

**Open since:** 2000

---

**Gross floor space:** 5,800m<sup>2</sup>

---

**Equipment floor space:** 3,301m<sup>2</sup>

---

**Major service providers on site:**  
 TeleCity hosts over 40 Telecom carrier providers in Amsterdam, please contact your account manager for the most recent overview.

---

**IXP hosted:** AMS-IX, NL-ix, XchangePoint.

**Contacts**

**Sales:** Mariska van Beukering.

---

**Operations:** Jeroen Schlosser, Operations Manager.



**Building specification**

The TeleCity Amsterdam South East site offers a secure, resilient environment for hosting customer platforms through the following utilities, connectivity, security, cooling/fire suppression and support specifications:

<b>Utilities:</b>	Power feed (Dual/Ring)	4.0 MVA
	Generators	3.7 MVA
	UPS	2.8 MVA
	Cooling	2.5 kW
	Lighting (operational/emergency)	500/2 LUX

**Connectivity:** TeleCity has two diverse routes consisting of ducts entering the building at either end of the facility: cables are routed securely to the ODF in the meet-me-room.

All cabling within the facility is controlled by TeleCity. Carrier feeds are diverse and secure.

All cabling is anonymous. TeleCity uses a cable infrastructure database which is updated every time circuits are added or removed.

**Security:** 24x7 on-site manned.  
 Customer access list, proximity card, escorted visitation.  
 CCTV throughout the facility.  
 Additional customer specific measures available as required.

**Cooling/fire suppression:**  
 Temperature of 20C (±2) in equipment zone.  
 Humidity of 50% (±10%).  
 VESDA fire detection system.  
 Double knock water mist suppression system.

**Support:** Rack Installation.  
 24x7 on-site engineering.  
 Remote hands.

